SANITARY AND TOWN PLANNING DIVISION, BANGALORE.

Dated 23rd May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to 2 P.M., of 1st July of 1929 for Laying Cast Iron Rising Main and Distribution System, in connection with Water Supply to Hunsur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer's Office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) only in cash as earnest money, and be superscribed "Tender for Laying Cast Iron Rising Main and Distribution System at Hunsur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne entirely by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for, and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer of Mysore, will be final and legally binding.

Abstract of quantities.

No.	Items of work	Per	Quantity
	Works to be carried out in Distribution system.		
1	Earthwork excavation and refilling, forming pipe trench in hard gravelly, clay and mooram soil.	C.yd.	2,711
2	Conveying from stores, laying, lead jointing and testing the cast iron pipes, specials including cuts and collor joints 5" cast iron pipes.	Joint	250
3	Do do 4"	,,	48
4	Do do 3"	,,	150
5	Conveying do do cement jointing 5" cast iron pipes	,,	25
6	Do 4" do	,,	25
7	Do 3" do	,,	551
8	Flange joints, belts, nuts and rubber insertion being supplied	,,	8
9	by the contractor 5".		
	Do 4"	,,	4
10	Do 3"	,,	10
11	Conveying from stores, laying and jointing galvanized iron pipes and specials including cutting and threading, etc., complete in a trench $1\frac{1}{2}'$ x $1\frac{1}{2}'$ and reforming the same 2" galvanized iron pipes.	R.ft.	992
12	Do do $1\frac{1}{2}$" do ...	,,	2,555
13	Do do 1" do ...	,,	3,475
14	Main bores in cast iron pipes $1\frac{1}{2}$"	Each	10
15	Do 1"	,,	20

No.	Items of work	Per	Quantity
16	Removing and resetting covering slabs of drains ...	S.ft.	100
17	Constructing gland cock cisterns as per type design and fixing road boxes.	No.	34
18	Surki concrete	C.ft.	213
19	Burnt brick in surki mortar	,,	174
20	Surki plastering	Sqr.	2·16
21	Burnt stone slab 4" thick 2 line dressed and fixed ...	Sq.ft.	78
22	Drilling holes in slabs and fixing M. S, Shutters with bolts, etc.	No.	6
23	Reinforced cement concrete slab 4½" thick with one edge rounded.	Sq.ft.	588
24	Cement concrete (1-2½-5)	C.ft.	133
25	Do slabs 6" thick (1-2-4)	Sq.ft.	91
26	Cement plastering ½" (1 to 3)	Sqr.	2·8
27	Fixing fountain with bolts and nuts...	No.	28
	Laying and Jointing 5" Raising Main.		
1	Farthwork excavation (gravel, moorum and clay soil) and refilling and forming pipe trench, etc., complete.	C.yd.	973
2	Do do in soft rock ...	,,	106
3	Do do hard rock with blasting ...	,,	106
4	Burnt stone jelly in surki mortar concrete	C.ft.	240
5	Burnt brick in surki mortar	,,	515
6	Burnt stone slabs 4" to 6" thick 2 line dressed and fixed ...	S.ft.	141
7	Do 6" thick two line dressed and fixed ...	,,	82
8	Do 4" to 6" thick one line dressed alround grooves cut for the seat of pipes and fixed.	,,	49
9	Surki mortar plastering	Sqr.	6·21
10	Constructing new stone revetment with jelly packing in the interstices.	C.yd.	114
11	Forming a foot-path on the line with the available earth ...	S.yd.	2,000
12	Preparing and fixing mile stones including painting ...	No.	2
13	Do furlong do ...	,,	7
14	Removing and refixing covering slabs of drains and culverts...	S.ft.	100
15	Fixing valve cistern covers with drilling 4 holes in slabs and fixing bolts in them with lead, etc., (only the covers will be supplied).	No.	5
16	Turfing	Sqr.	2
17	Conveying from stores, laying and jointing 5" cast iron pipes with lead including cuts and collor joints.	Joint	380
18	Do flange joints, bolts, nuts and rubber insertion being supplied by contractor.	,,	20

H. F. MARKER,
Executive Engineer.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

Notice No. 14163, *dated* 29*th May* 1929.

1. - Sealed tenders for the supply of Wheat Bran Barley, Oats and other miscellaneous articles required for the Government Stud Farm at Kunigal, during the year 1929-30, will be received by the undersigned up to 12 noon on the 20th June 1929.

2. A sum of Rs. 300 in cash towards earnest money should be remitted to the Officer in charge of the State Huzur Treasury, Bangalore, with challans duly filled in by the tenderers, the fact of such remittance being noted in the tenders sent to this office. Cheques will nof be received by the State Huzur Treasury Officer, on this account.

3. Forms of tender and challans for remitting earnest moneys may be obtained from the Office of the Secretary, Stores Purchase Committee, on payment of Rupees three only (in cash) being the price fixed for the form.

The forms will not be sent by V. P. P.

By Order,
E. V. GANAPATHI IYER,
Secretary,